SKYSPANSHADE
COMMERCIAL UMBRELLAS AND SHADE STRUCTURES

Vista Umbrella

Maintenance

Vista Cantilever Umbrella Maintenance Schedule

This should be carried out bi-annually

1. Check that canopy edge cable is seated in plates correctly (the cable should be in between the intermediate plate and the corner plate bolt).

2. Nuts and bolts should be checked and tightened as needed. Loctite applied to all bolts if found loose.

3. Fabric is positioned correctly over top plate.

4. Bolts at base plate are tightened as needed using a 19mm socket (you may need to remove plastic plug to reach nuts).

5. Jack and winding mechanism travel freely (by winding umbrella up and down).

6. Check there is ample amount of grease. This must be done with canopy in the up position then wind mechanism up and down once.

7. Check corner bolts that hold canopy down and tighten (using a 5mm Allen key).

8. Check umbrella is wound up until the edge cable in the canopy is tight, there is no need to go to stop, this extra travel is to allow stretch in canopy and edge cable.

9. Pivot locking bolt should be kept tight in line with the locking hole at all times, use spanner to assist supplied tool.

SKYSPAN SHADE
Office / Factory Unit 1, 4 Old Pacific Highway, Yatala, Queensland 4207, Australia
Tel: +61 (0) 7 3804 6288 Email: sales@skyspanshade.com.au
www.skyspanshade.com.au